

CORONAVIRUS DISEASE 2020 – WORKPLACE STALLED SITE PLAN

Construction Site Shutdown

This document will serve as a guideline in the event we are directed by a client, an executive, or a governmental authority to cease or suspend all construction activities on our projects. The following list below shall serve as a general guideline for a project shutdown or stall. Check with the local jurisdiction for local requirements.

GENERAL

- Plan periodic off-site meetings and/or telephone conference calls with clients, design team, contractors, unions, etc. for status and any new measures. It may be advisable to appoint a primary contact person and accountability system for employees to report health issues.
- Maintain separate cost identifications and documentation for shut down effects and maintenance.
- Continuance of accounting, requisitions, payments, etc. shall be managed off site.
- Ensure all emergency, temporary, and permanent egress is maintained and unobstructed prior to site closure, including ladders, scaffold stairs, graded ramps.
- Ensure all essential utilities to the site maintenance are maintained and clearly marked up to the point of closure. Coordinate any shutdowns with the applicable authority and/or subcontractor.
- Ensure any locked-out utilities (water, steam, electric, etc.) must have properly completed tagging including name of contractor, name of individual who placed the lock, and most importantly, his or her phone number. There's no guarantee that the returning workforce personnel will be the same as the one that left the project.
- Make certain interior spaces are water-tight to the greatest extent possible as mold growth is a potential concern when a building is left unattended.
- All required temporary or permanent egress shall be maintained and unobstructed.
- All essential utilities to the site maintenance shall be maintained.
- Ensure public sidewalks are maintained safely in accordance with federal, state and local governmental authorities, free of ice, snow, grease, debris, tripping hazards, etc.
- All traffic control protection shall remain in a state of readiness.
- Temporary lighting shall remain illuminated.
- Temporary plumbing systems shall be shut down and drained to prevent freezing.
- As applicable, the construction site must be enclosed with a construction fence in accordance to the local regulatory agency or department.
- Schedule weekly inspections, if permitted/warranted, of the site to ensure compliance.
- Place a sign at the entrance with emergency contact information of at least 3 people that can provide accurate information and/or access to the site.
- Notify town emergency personnel (fire, police, rescue) that the site will be inactive and, if possible, provide a copy of the Emergency Action Plan and site map, should they need to access a site in an emergency.
- Require a watchperson, 24/7 video surveillance, and/or other types of electronic security measures as deemed appropriate by regional management and if permitted by local authorities.
- A rodent control plan shall be implemented as applicable to the location.

EXCAVATION FOUNDATION

- Un-shored earth cuts shall be sloped or benched to an effective stable angle of repose of 45

CORONAVIRUS DISEASE 2020 – WORKPLACE STALLED SITE PLAN

degrees or flatter and stabilized to prevent erosion. Angles steeper than 45 degrees or adjacent to existing buildings or public ways will not be permitted without a geotechnical report by licensed professional engineer verifying stability of soil at proposed angle.

- Soil shall be sloped away from adjoining structures, lots, and public sidewalk, for proper drainage.
- Support of excavation shoring shall be inspected by a licensed engineer for conformance to and completeness in accordance with design. All elements of installed support of excavation shall be completed such as tiebacks, rakers, footing blocks, walers. If work cannot be completed in areas of installed excavation supports, a licensed engineer shall provide a signed and sealed report verifying current stability of excavation and inspect prior to project closure. Lagging boards shall be inspected against soil loss. Support of excavation shoring shall be left in a stable position.
- Underpinning shall be inspected by a licensed engineer for conformance to and completeness in accordance with the approved design. All excavated underpinning piers shall be concreted, and load transferred to the pier. Unless underpinning is braced by rakers or tie backs, fill shall be placed against all exposed underpinning, to prevent lateral displacement. Licensed engineer shall provide a signed and sealed report verifying current stability of underpinning and of structure that was underpinned and shall inspect prior to shutdown to ensure sustained stability. Underpinning shall be left in a stable position.
- Excavations/Foundations shall be maintained dry up to the point of closure. Where pumping operations were employed, a Licensed Engineer shall evaluate foundation uplift and waterproofing prior to authorizing cessation of pumping operations. *Note: Department of Environmental Protection (DEP) permits are required for pumping into certain city wastewater removal systems and other permits are required for pumping into natural water bodies. Check with your local authorities.*
- All heavy construction equipment and storage (trailers, shipping containers, excavators, backhoes, etc.) shall be locked, secured and either removed from the site or relocated back from edge of excavation a distance equal to 1 1/2 depth of excavation, unless engineer of record certifies that SOE shoring is designed for the surcharge load from equipment.
- The construction excavation/foundation site must be enclosed with a construction fence or other means of protection in accordance to the local regulatory agency and or department. It may be necessary to utilize a hard barrier (steel fencing), if the site is unable to be secured by other measures.

CRANES/HOIST

- Secure all cranes (Tower, crawler, hydraulic, etc.) in accordance to the manufacturer's recommendations at the end of each workday. Where possible all booms should be lowered.
- Hoists and Elevators to remain in emergency readiness for local fire and police department.
- Secure all hoist and/or other lifting machinery.

SUPER STRUCTURE

- All formwork and re-shores shall be removed, provided concrete has reached its design strength. If re-shores are to remain, they shall be periodically checked as possible during project inspections to make certain they are snug. Perimeter re-shores shall be tied back as per local regulatory agencies and/or department.
- All steel members secured by a minimum of 2 bolts per connections or greater as determined by

CORONAVIRUS DISEASE 2020 – WORKPLACE STALLED SITE PLAN

the steel erection engineer.

- Ensure all metal decking is secured.
- All material such as bolts, shear studs, welding material, gas tanks, and other consumable secure away from exterior and interior building edges.
- Ensure all working decks are cleaned at the end of every workday.
- All equipment such as compressors, generators, crabs, lifts secured away from exterior and interior building edges.
- The fire standpipe must remain in a state of readiness.
- All scaffolding and debris netting, sidewalk sheds, and temporary walkways shall be inspected for compliance, including required illumination. Loose scaffold planking shall be removed or properly fastened prior to closure. Scaffold tiebacks shall be maintained and inspected for signs failure prior to closure.
- All adjoining property protection shall be maintained/reviewed prior to closure.
- All guardrails systems, vertical netting, horizontal netting floor, wall, and roof openings protection shall be in place and secure.
- All construction debris must be removed from the project All volatile liquids or gases (oxygen, acetylene, gasoline, etc.) shall be removed from site, except those used to fuel required emergency power generation equipment. Storage shall be in accordance with the applicable local, state, and federal, fire code, rules and regulations.
- All construction materials shall be safely stored. All light-weight materials susceptible to becoming wind-borne shall be removed from site, tied down, or ballasted.
- All required temporary or permanent egress shall be confirmed clear and unobstructed.
- All required temporary or permanent exit signs and exit illumination sign shall be operating/maintained prior to closure.
- Ensure all bolts, nuts, connections, etc. on any steel erection are tight and secure.

CONTROL

Housekeeping

Upon completion of the above noted, a general housekeeping operation will be performed for the entire project. This is to include all project offices, sub-contractor's trailers and shanties.

Special focus will be place on cleaning and disinfecting surfaces which come in direct human contact. Debris from these areas will be removed.

Targeted areas/items are but not limited to:

- Site entrance access gates and doors
- Turnstiles entrance
- Tools
- Hoist Cars
- Office/shanties furniture, keyboards, phones, printer, etc.
- Heavy equipment
- Fire extinguishers
- Medical cabinets
- Phone
- Copy machine

CORONAVIRUS DISEASE 2020 – WORKPLACE STALLED SITE PLAN

- Water cooler
- Coffee maker
- Toilets
- White board
- ***Installing high-efficiency air filters***

All workers performing housekeeping must wear the appropriate personal protective equipment (gloves, respiratory protection, etc.) Outside environmental services can be utilized to performed general housekeeping and/or sanitize project field and remote offices. Safety Data Sheets should remain on site for all cleaning products. All locations shall be cleaned prior to closure.

Project Review

The lead Superintendent and designated SH&E professional shall walk through the project and ensure all the aforementioned items have been completed. Other site-specific items may need to be accomplished in addition to those mentioned.

The Project Executive shall keep the Regional Office apprised of the project closure status, daily. Secure all project files and the project office. Remove those that are deemed necessary.